



Complex
Automation
Systems GmbH

BILIKI

Data Center

Technical Consultation

Data Center Design

Tier III+ Certification Scope

BASIS OF DESIGN

Document #

GGE-CAS-DES-BOD-C02

27.10.2025

BASIS OF DESIGN (BoD)

Project: Biliki Data Center Unit (DCU)

Location: Isani-Samgori District, Tbilisi, Georgia (adjacent to Kura River)

Prepared by: CAS GmbH

Date: October 2025

Document Code: GGE-CAS-DES-BOD-C02

Contents

<u>BASIS OF DESIGN (BoD)</u>	1
<u>1. PROJECT DATA AND TARGETS</u>	2
<u>2. CLIMATIC DESIGN CONDITIONS (TBILISI)</u>	4
<u>3. BUILDING PHYSICAL PARAMETERS</u>	4
<u>Group 2: Enterprise Suites B and C</u>	5
<u>(2 rooms):</u>	5
<u>4. ELECTRICAL POWER TOPOLOGY (Phase 1)</u>	5
<u>Fuel system</u>	6
<u>5. MECHANICAL COOLING SYSTEM</u>	7
<u>River-water free cooling & ground-thermal (BILIKI DCU, Tbilisi)</u>	7
<u>6. FIRE PROTECTION AND SAFETY</u>	8
<u>7. SECURITY AND ACCESS</u>	8
<u>8. NETWORK AND CONNECTIVITY</u>	8
<u>9. TIER III COMPLIANCE</u>	9
<u>10. SUSTAINABILITY</u>	9
<u>SUMMARY</u>	9

1. PROJECT DATA AND TARGETS

Total IT capacity: 5.635 MW / 407 racks

Functional mix:

Quantum (AI): 2.5 MW, 100 racks, direct-to-chip liquid cooling

Enterprise Suites A-C: 1.47 MW, 132 racks, in-row cooling

Hub: 0.665 MW, 95 racks, in-row cooling

VIP: 1.0 MW, 80 racks, in-row cooling

The project was structured in phases, and each phase was subdivided into specific groups.

Phase 1 comprises two implementation groups:

- **Group 1:** VIP (5 halls)
- **Group 2:** Enterprise Suite A and Hub

Phase 2 comprises also two implementation groups:

- **Group 1:** Quantum (AI)
- **Group 2:** Enterprise Suites B-C

Certification target: Uptime Institute Tier III Certified

 casystems.at	Project BILIKI Data Center	Client GGE	
	Drawing title Basis of Design	Pr. ref. BOD-C02	Date Oct 27, 2025
		Sheet size A4	Sheet 2

Design objectives:

Concurrent maintainability (CM) on all systems

Annualized PUE ≤ 1.5

Energy source: 3.7 MW Mtkvari HPP (Archimedes screw + IRD dam),
100% renewable and City Utility service.

Sustainability: LEED Gold, Hydropower Sustainability Standard, CO₂
credit certification



Project

BILIKI Data Center

Client

GGE

Drawing title

Basis of Design

Pr. ref.

BOD-C02

Date

Oct 27, 2025

Sheet size

A4

Sheet

3

2. CLIMATIC DESIGN CONDITIONS (TBILISI)

Elevation: 427 m AMSL
Max dry bulb: +40.2 °C
Min dry bulb: -11.2 °C
Summer design (0.4%): DB 35.2 °C / WB 22.8 °C
Winter design (99.6%): DB -4.7 °C
Average annual DB: 14.4 °C
Seismicity: Zone VIII, PGA 0.25-0.27 g

3. BUILDING PHYSICAL PARAMETERS

Elevation references

Basement -2 (Cooling Plant): -11.00 m
Basement -1 (Power/MEP): -5.55 m
Ground Floor (IT Halls): ±0.00 m
First Floor (Offices / NOC / VIP): +5.40 m
Roof (finish): +10.90 m
Satellite antenna: +16.00 m

Raised floor heights

IT halls: 450 mm
Corridors / MMRs: 450 mm

Clear heights

IT halls: ≥ 4.5 m
Offices / NOC: ≥ 3.5 m

 casystems.at	Project	Client	
	BILIKI Data Center	GGE	
Drawing title	Pr. ref.	Date	
	BOD-C02	Oct 27, 2025	Sheet
Basis of Design	Sheet size	A4	4

Phase 1	Phase 2
Group 1: VIP (5 rooms):	Group 1: Quantum (AI)
<p><i>IT load: 1,000 kW</i> <i>IT area: 385 m²</i> <i>80 racks – average 12.5 kW/rack</i></p>	<p><i>IT load: 2,500 kW</i> <i>IT area: 471 m²</i> <i>100 racks – average 25 kW/rack</i></p>
Group 2: Enterprise Suite A and Hub (2 rooms):	Group 2: Enterprise Suites B and C (2 rooms):
<p><i>IT load: 1,385 kW</i> <i>IT area: 671 m²</i> <i>167 racks – average 8.5 kW/rack</i></p>	<p><i>IT load: 750 kW</i> <i>IT area: 194 m²</i> <i>60 racks – average 12.5 kW/rack</i></p>
Subtotal	Subtotal
7 rooms IT load: 2,385 kW IT area: 1,056 m² 247 racks Average density: 10.5 kW/rack	3 rooms IT load: 3250 kW IT area: 665 m² 160 racks Average density: 18.75 kW/rack

Total

10 rooms
IT load: 5,635 kW
IT area: 1,691 m²
407 racks
Average density: 13.4 kW/rack

 casystems.at	Project BILIKI Data Center	Client GGE	
	Drawing title Basis of Design	Pr. ref. BOD-C02	Date Oct 27, 2025
		Sheet size A4	Sheet 5

4. ELECTRICAL POWER TOPOLOGY (Phase 1)

Sources and transformation

Dual independent utility + HPP feeds

Transformers: 4 total (2 per group)

- Each group includes 1 × 3000 kVA dry-type units
- A/B segregation, 2N configuration

Generators

4 × 2500 kVA total (2 per group)

UPS and batteries

Modular static UPS (N+1 per side)

LiFePO₄ battery banks, ≥10-15 min autonomy

Optional flywheel bridge prepared

Fuel system

Bulk + day tanks per Group

Dual transfer pumps (duty/standby) per line

Fuel storage tank: 20 t

Day tank: 1 m³

Fuel consumption: 563.8 L/h.

Cross-feed with isolation valves

≥72 h autonomy



Project

BILIKI Data Center

Client

GGE

Drawing title

Basis of Design

Pr. ref.

BOD-C02

Date

Oct 27, 2025

Sheet size

A4

Sheet

6

Distribution and switching philosophy

- Independent A/B buses from source to PDU
- Normal operation: incomers NC, bus ties NO
- Maintenance transfer: NO→NC→NO sequence ensures CM
- Generator incomers NC only when on generator supply

5. MECHANICAL COOLING SYSTEM

Hybrid system: direct-to-chip liquid for AI, in-row CRAH for enterprise/VIP/host

River air tunnels (<26 °C) for passive free cooling for Chiller, UPS and battery rooms

Chiller plant (N+1), dual segregated loops

River-water free cooling & ground-thermal (BILIKI DCU, Tbilisi)

A hybrid cooling strategy that leverages our river-adjacent site with a closed-loop, no-contact Kura River free-cooling system plus a complementary ground-thermal field. The approach materially cuts mechanical cooling energy, water use, and noise, supporting the OPR target with annualized PUE ≤ 1.5. The river system uses screened intake and plate-heat-exchanger (PHE) trains (no mixing with river water); metallurgy and concrete protection are selected for the site's chemistry (elevated sulfates/chlorides), ensuring longevity of assets and civil works. The ground-thermal provides a stable heat sink/source year-round, extending free-cooling hours and smoothing HPC direct-to-chip and chilled-water loads—while preserving concurrent maintainability and independent headers/pumps for Tier III topology. The scheme respects the waterfront planning context and permits framework for the Mtkvari corridor.



Project

BILIKI Data Center

Client

GGE

Drawing title

Basis of Design

Pr. ref.
BOD-C02

Date
Oct 27, 2025

Sheet size
A4

Sheet
7

6. FIRE PROTECTION AND SAFETY

Detection: VESDA, zoned smoke/heat sensors

Suppression: Inergen/Novec in IT halls, pre-action water mist in plant areas

Compartments: 2-hour fire-rated walls between A/B paths

Life safety: dual staircases, 10 t freight elevators for chiller/genset transport

7. SECURITY AND ACCESS

Multi-layered access: perimeter → gate → building → mantrap → hall

Biometric + dual-factor for IT spaces

24/7 CCTV with SOC integration

NOC blast-resistant and acoustically insulated

8. NETWORK AND CONNECTIVITY

Dual fiber routes along Tbilisi railway corridor

Meet-Me Rooms: 2 × fully diverse (A/B)

Latency: < 30 ms to Istanbul, < 40 ms to Dubai



Project

BILIKI Data Center

Client

GGE

Drawing title

Basis of Design

Pr. ref.

BOD-C02

Date

Oct 27, 2025

Sheet size

A4

Sheet

8

9. TIER III COMPLIANCE

Tier III - Concurrent Maintainability

All systems designed N+1 minimum

Maintenance of any single component without IT impact

Dual independent A/B paths with ties normally open

Availability targets

Tier III: 99.982% (~1.6 h downtime/year)

10. SUSTAINABILITY

100% renewable hydropower baseline (Phase 1)

Onsite PV array on roof (10-15% supplemental)

LEED Gold / HSS certification

Carbon credit monetization (Verra/JCM)

SUMMARY

The Biliki DCU is a 5.635 MW IT facility with a total gross building area of 16 000 m², designed for Tier III Certification. Its architecture, power and cooling topology, and operational concepts ensure concurrent maintainability, renewable energy integration, and PUE ≤ 1.5.



Project

BILIKI Data Center

Client

GGE

Drawing title

Basis of Design

Pr. ref.
BOD-C02

Date
Oct 27, 2025

Sheet size
A4

Sheet
9